

WDCMS Networking & Data Logging Set Up/Commissioning

General Requirements –

- Standard Wallgate Commissioning is a requirement ahead of WDCMS Networking & Data Logging Set Up/Commissioning.
- 14 days notice required before commissioning commences, sufficient time must be allowed for completion of the works before project handover, contact Wallgate to be advised of expected duration.
- Pre-commissioning review/meeting with appointed Commissioning Manager, to confirm commissioning requirements.
- Full installation and certification of all data cabling associated with Wallgate systems, and detailed site information, all as defined in product manual.

Commissioning Service Includes^(*) –

1. Configure the PC(s) (if supplied) and the front end software as per the pre-confirmed requirements. Including setting of user access levels within WDCMS.
2. Test for correct operation of software, as defined in the WDCMS product manual, including physical confirmation of remote control throughout the network.
3. Testing of auxiliary inputs to EGI-01 gateways.
4. On-site demonstration and system handover with the client.
5. Leave in full working order, ready for use.
6. Commissioning Report, Certificate and copies of all data files will be supplied.
7. A data stick containing copies of WDCMS software, product manuals and all files will be provided.

(*) Please note the above service does not include –

- Installation of any data cabling.
- Any works associated with physical installation or replacement of new products.
- The making of any final connections to mains services (e.g. power, water, waste, etc.).
- Rectification of any defects associated with installation of any network related items.